BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule-B

NAME OF THE WORK: Construction of RCC drain in Adjusted to dasarahalli road and cross at Kalyana nagara in ward no. 13

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per the direction of Engineer-in-charge of the work.	Cum	523.26	83.16	Rupees Eighty Three and Sixteen Paise Only
2	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Cum	87.21	5139.94	Rupees Five Thousand One Hundred Thirty Nine and Ninety Four Paise Only
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Cum	310.32	6083.34	Rupees Six Thousand Eighty Three and Thirty Four Paise Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. complete as per the direction of Engineer-in-charge of the work.	Qtls	188.62	6851.31	Rupees Six Thousand Eight Hundred Fifty One and Thirty One Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL , BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specification. complete as per the direction of Engineer-in-charge of the work.	Sqm	2454.80	301.04	Rupees Three Hundred One and Four Paise Only
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & complete as per the direction of Engineer-in-charge of the work.	Sqm	63.72	1600.00	Rupees One Thousand Six Hundred Only
##	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work.	Cum	523.26	81.73	Rupees Eighty One and Seventy Three Paise Only

EXECUTIVE ENGINEER
BENGALURU-560 016

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer
Dasarahalli Division